



AC TRANSMISSION MAIN REPLACEMENT - PHASE 1

**NORTHEAST SAMMAMISH SEWER AND
WATER DISTRICT**

- THIS PROJECT WILL REPLACE THE EXISTING WATER SYSTEM AS SHOWN IN THE FIGURES BELOW AND THE RIGHT AND WILL INCLUDE THE FOLLOWING:
- REPLACE EXISTING WATER MAIN, WATER SERVICES, FIRE FIRE HYDRANTS AND OTHER APPURTENANCES
 - ALIGNMENTS SHOWN SCHEMATICALLY, ALL WATER MAIN REPLACMENT WORK IS WITHIN THE ROADWAY
 - MINOR DISTURBANCES OF EXISTING LANDSCAPING FOR THE NEW WATER METERS, HYDRANTS AND APPURTENANCES
 - INTERRUPTION OF WATER SERVICE AS THE NEW SYSTEM IS CONNECTED TO EXISTING CUSTOMER SERVICE LINES
 - PAVEMENT TRENCH PATCHING, FOLLOWED BY GRIND AND OVERLAY OF ROADWAYS
 - ONE WAY ALTERNATING TRAFFIC WILL BE PROVIDED DURING THE COURSE OF CONSTRUCTION IN THE AREA OF WORK
 - IT IS ANTICIPATED THAT THIS WORK WILL TAKE APPROXIMATELY 6 MONTHS TO COMPLETE



LEGEND		
	=	PROPOSED WATER MAIN
	=	ROAD CENTERLINE

